			(ווו) פווטופווטוווט			rasteller schedule				DF/SP	S-P-F
						CMU/Concrete Wall ⁴		Truss/Rafter		Allowable Loads (Lbs.)	Allowable Loads (Lbs.)
MiTek Stock No.	Ref. No.	Steel Gauge	w	L	Lſ	Qty	Screw Anchor ^{2,3}	Qty	Type ⁵	Uplift 160% ¹	Uplift 160% ¹
HTWM16	HTSM16, MTSM16	14	1-1/4	16	5-3/4	4	1/4" x 1-3/4"	8	10d x 1-1/2	1225	1145
HTWM20	HTSM20, MTSM20	14	1-1/4	20	7-3/4	4	1/4" x 1-3/4"	8	10d x 1-1/2	1225	1145
1) Allowable loads have been increased 60% for wind or seismic loads; no further increase shall be permitted. 2) Use DeWalt 1/4" x 1-3/4" Screw-Bolt™+; or equal, installed in accordance with manufacturer's specification. 3) DeWalt 1/4" x 1-3/4" Screw-Bolt™+ are not supplied with HTWM straps. 4) Grout or concrete compressive strength shall be 2.500 psi or greater at 28 days.											

Eastener Schedule

Dimensions (in)

5) **NAILS:** 10d x 1-1/2 nails are 0.148" dia. x 1-1/2" long.